

**KERALA AGRICULTURAL UNIVERSITY
COLLEGE OF AGRICULTURE; PADANNAKKAD**

No. G1-927/2023

Dated:27.02.2023

TENDER NOTICE

Tender Number	G1/927/2023
Cost of Tender form	0.2% of the quoted amount rounded to the nearest multiple of 100, subject to a minimum of Rs.400 and maximum of Rs.1500 + GST 18%
Amount of EMD to be paid	1% of the total cost of work (Minimum Rs.1500/-)
Last date and time for receipt of tender	14.03.2023, 11.00 A M
Last date and time for opening of tender	14.03.2023, 11.30 A M
Date up to which the rates are to remain firm for acceptance	Up to 31/03/2023
Designation and address of officer to whom the quotation is to be addressed	Dean College of Agriculture, Padannakkad
Place of work	College of Agriculture, Padannakkad
Superscription: "Construction of UG Laboratry for Plant Pathology Department "	

Sealed competitive tenders are invited for the Construction of UG Laboratry for Plant Pathology Department

Name of work: Construction of UG Laboratry for Plant Pathology Department							
Sl No	Description	No.	L	B	D	QUANTITY (m ²)	UNIT
1	15.7.4 Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar						
	Existing Floor demolishing	1	17.24	10.00	0.30	51.72	
			Total qty			51.72	M2
2.	11.41.2 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS :15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600 x 600 mm.						
	Floor	1	16.00	7.00		112.00	
	skirting	2	16.00	0.10		3.20	
		2	7.00	0.10		1.40	
			Total			116.60	M2
3.	21.1.1.1 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminnium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS : 1868, Minimum anodic coating of grade AC 15)						

	Door (1.50x2.10m)	2	1.00	1.50	2.200	6.60	
	Vertical shutter	2	2.00	2.10	2.200	18.48	
		2	3.00	1.50	0.890	8.01	
		2	4.00	2.10	0.890	14.95	
	window bottom (1.50x1.50m)	6	1.00	1.50	1.039	9.35	
	top	6	1.00	1.50	1.039	9.35	
	Vertical shutter	6	2.00	1.50	1.039	18.70	
		6	4.00	0.85	0.890	18.16	
		6	4.00	1.50	0.890	32.04	
Total						135.64	Kg
4.	21.2.1 Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS : 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in- Charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side						
	Door (1.50x2.10m)	2	1.00	1.50	0.9		
Total						0.9	M2
5.	21.3.1 Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness						
	Door (1.50x2.10m)	2	1.50	1.20	3.6	12.96	
	window(1.50x1.50m)	6	2.00	0.85	1.5	15.3	
Total						28.26	M2
6.	12.26.2 Providing and fixing plain Multipurpose Cement board (High Pressure steam cured)as per IS : 14862, with suitable screws for fibre cement board in ceiling etc. complete (frame work to be paid separately) :6 mm thick Cement bonded wood particle boardas per IS:14276						
	south&north wall	2	2.00	16.00	3.300	211.20	
	east &west wall	2	2.00	7.00	3.300	92.40	
	deduct doors	-2	2.00	1.50	2.100	-12.60	
	windows	-6	2.00	1.50	1.500	-27.00	
Total						264.00	M2
7.	10.16.2 Steel work in built up tubular (round , square or rectangular hollow tube etc.) trusses etc. including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc, completed Hot finished seamless type tubes						
	vertical 60x40x1.60	1	40.00	3.30	2.450	323.40	
	horizontal	1	4.00	46.00	2.450	450.80	
Total						774.20	kg
8.	13.48.1 Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications: Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of special primer applied @ 0.75 ltr /10 sqm						
	wall south and north side	2	2.00	16.00	3.30	211.20	
	east &west wall	2	2.00	7.00	3.30	92.40	
	deduct doors	-2	2.00	1.50	2.10	-12.60	
	windows	-6	2.00	1.50	1.50	-27.00	
Total						264.00	M2

Terms and Conditions: -

1. Tender form

The Tender form shall be downloaded from the following link in the internet www.kau.in/tenders or coapad@kau.in. The same should be submitted duly signed along with other documents.

2. Earnest Money Deposit

An EMD 1% of the total work charges should be remitted by separate DD drawn in favour of Dean, College of Agriculture, Padannakkad.

3. The cost of tender form, GST and EMD will be accepted by way of separate DDs in favour of Dean College of Agriculture, Padannakkad.

Agreement:-

4. The tender should be accompanied by an Agreement in Kerala stamp paper worth Rs.200/- (Rupees Two Hundred only) in the format that can be downloaded from the website www.kau.edu/tenders or coapad@kau.in
5. The sealed cover containing the tender document should be superscribed as “**Construction of UG Laboratory for Plant Pathology Department**”. The cover should contain the DDs for tender cost, GST, EMD and the Agreement as mentioned above.
6. The successful tenderer should execute an agreement in Kerala Stamp paper worth Rs. 200/- (Rupees Two Hundred only) and furnish a security deposit of 5% of cost of the rate quoted in the form of term deposit/bank guarantee /demand draft drawn in favour of Dean, College of Agriculture Padannakkad, Pin-671314, Kasaragod District payable at the State Bank of India, Nileshwar branch when directed from this office.
7. The rate, tax and other charges if any should be separately stated.
8. The Dean has the right to accept or reject any or all of the offers without assigning any reason.
9. The successful tenderer shall initiate the work within one week of award and should complete the work within 2 weeks.
10. If any harthal/strike/any unexpected holiday occurs on the date of opening of tender, the tender will be opened at the same time on the next working day.
11. All the rules and regulation applicable to government tender will be applicable to this tender also.

Special Conditions

1. Tender insisting payment in advance either full or part for releasing the documents through bank are liable for rejection.
2. Payment will be made after satisfactory completion of the work.
3. Time to time Government Orders regarding GST will be applicable to this Tender also.
4. The decision of the under signed in tender procedures will be final and binding.
- Enquiries if any may be mailed to coapad@gmail.com office hours or contact 04607-2280616 on working hours.

Sd/-
Dr.Sajitha Rani.T
Dean

To

1. Notice Board (College/ Farm) / KAU website/ College website
2. Village Office (Kanhangad/Nileshwar)
3. Municipality (Kanhangad/Nileshwar)
4. Regional Agricultural Research Station, Pilicode

Copy to: 1. Dr.Sainamole Kurian.P, Professor & Head (Plant Pathology).

2. Work Committee members
3. Cash Section

//Approved for Issue//


Section Officer